



### **ADDENDUM NO. 3**

**To:** Prospective Bidders  
**From:** Gary Walton  
TurnerBatson Architects, P.C.  
**Date:** November 30, 2018  
**Re:** Bluff Park Pavilion  
Architect's No. 2806

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated October 03, 2018 as noted below. The Bidder must acknowledge receipt of this Addendum by statement of receipt indicated on the Proposal Form. Failure to do so may subject bidder to disqualification.

#### **BIDDING REQUIREMENTS:**

1. NONE

#### **GENERAL CLARIFICATIONS:**

2. NONE

#### **SPECIFICATIONS:**

3. NONE

#### **DRAWINGS:**

4. Added Column Wrap Detail Sketch – which shows installing the 1x8 fiber cement column wrap trim in a manner that will allow the electrical receptacles to be recessed. Receptacles shown on Electrical Drawings. Install receptacles 3'-0" A.F.F.

#### **END OF ADDENDUM**

1X8 FIBER-CEMENT TRIM.  
ATTACH TO COLUMN IN A  
MANNER THAT WILL  
ALLOW ELECT RECEPTICLE  
TO BE RECESSED.

8 1/4"

RECESSED  
ELECT RECEPTICLE  
SEE ELECT DWGS.  
MOUNT RECEPT. 3'-0" A.F.F.

STEEL COLUMN  
SEE STRUCTURAL

WOOD BLOCKING AS REQ'D

# COLUMN WRAP DETAIL

NO SCALE