

ADDENDUM NUMBER TWO
TO THE CONTRACT DOCUMENTS FOR CONSTRUCTION OF
NORTH HIGHLAND ELEMENTARY SCHOOL
JEFFERSON COUNTY BOARD OF EDUCATION

This addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated January 25, 2019.

This Addendum consists of one (1) page and RFI Log.

GENERAL

ITEM 01 UPDATED BID DATE

1. **BID DATE** has been changed to **Tuesday, March 19th at 2:00pm CST.**

ITEM 02 BIDDER RFI LOG

1. **ATTACHED.**

ITEM 03 SUBSTITUTION REQUEST

1. **APPROVED** substitutions are as follows:
 - a. **Mitchell Metals** - Aluminum Walkway Covers & Canopies

- END OF ADDENDUM -

BIDDER RFI LOG

Item No.	Reference Sheet	Reference Detail	Information Requested	Date Submitted	Answered by	Date Answered	Information Provided by Design Team
1			Confirm whether or not there is an existing ADEM Permit with the Demolition Contractor	2/19/2019	DAI	2/28/2019	No, the Demolition Contractor does not currently have an ADEM permit.
2			Clarify whether or not existing transformer is still in place.	2/19/2019	DAI	2/28/2019	Existing transformer is not in place.
3			Confirm whether or not existing water tap is intact and turned off.	2/19/2019	DAI	2/28/2019	No, existing water tap is not intact. A new tap is required. See Drawings.
4			Confirm whether or not a new fire tap is needed.	2/19/2019	DAI	2/28/2019	A new Fire tap is required. See Drawings.
5			At openings 001, 003, 004, 005, 103-1, 103-2, 103A, 109-1, 303, 701A, C200, C300, C700A-1, C700A-2, C700B, the frames are noted to have a 4" jamb face on the door schedule. Is this correct?	3/1/2019	DAI		Yes, intent is for doors in masonry opening to have frames that are a coursing dimension.
6			Opening OP-603 is listed on the door schedule as a hollow metal door but does not provide elevation or frame elevation. Please advise	3/1/2019	DAI		OP-603 is a gyp opening and does not require a door or door frame.
7			At openings C600, C700A-1, C700B, the door schedule notes these doors to have "WD" elevations, however, these doors are listed as hollow metal. Please advise.	3/1/2019	DAI		Doors C600, C700A-1, and C700B should be wood. Will be revised before bid.
8			At aluminum openings 113-1, 601-2, 113A, 703, 113B, 113C, 609, door hardware does not appear to be for aluminum openings. Please advise.	3/1/2019	DAI		Hardware for these doors will be revised before bid.
9			Opening 001 is a single opening scheduled for hardware associated for a pair of doors. Please advise	3/1/2019	DAI		Hardware for 001 should be for a single door. Will be revised before bid.
10			Hardware set 42.0 is for FEMA shutters, however, there doesn't appear to be shutters on the floor plan, nor are they listed in the door schedule. Please advise.	3/1/2019	DAI		No FEMA shutters are included in this school. Will be removed before bid.
11			Are cased openings to have hollow metal frames?	3/1/2019	DAI		No, cased openings do not have hollow metal frames.
12	A3.70	F-1 & F8	Detail (F1)A3.70 and (F8)A3.70 shows sheet membrane waterproofing and dampproofing specified but there is no spec section for it. What products are to be used and is this to continue across the entire stem wall?	3/1/2019	DAI		FAMAB and flexible flashing should be installed as required in section 07 2500 Weather Barriers.
13			Is a waterproofing product to be installed under the gym floor slab to avoid mold or adhesion of the modular sports floor in the future? Such as Florprufe120	3/1/2019	DAI		No waterproofing is required under the modular sports flooring.
14							
15							
16							
17							
18							
19							
20							
21							
22							
23							
24							
25							
26							
27							
28							
29							
30							
31							
32							
33							