



105 W. 2<sup>nd</sup> Street  
Tuscumbia, AL 35674  
T (256) 248-7030  
F 1-866-225-7488

**PROJECT:** Hwy 25 Streetscape Improvements  
Town of Wilsonville  
ALDOT Project No. TAPNU-TA17(907)

**ADDENDUM NO.** Two (2)

**DATE:** May 13, 2020

**TO:** All Record Holding Contract Documents

This Addendum is issued to all registered plan holders pursuant to the Conditions of the Contract.

This Addendum serves to clarify, revise, and supersede information in the Project Manual, Drawings, and previously issued Addenda. This addendum and its attachments shall become a part of the plans and specifications and shall apply to the bid proposals for the above named project.

The bidder(s) shall notify all affected subcontractors, material suppliers, and others to incorporate necessary cost and schedule updates, to the bid proposal and the work changes affected by this Addendum.

The Bidder shall acknowledge receipt of this Addendum in the appropriate space on the Bid Form. Bidders must also acknowledge receipt by email to [wendy@kelleynetwork.com](mailto:wendy@kelleynetwork.com).

In the event of conflict between plans and specifications and this addendum, the addendum shall take precedence. Any modifications necessary to incorporate the revisions shall be included in the appropriate bid prices. The bid documents are hereby corrected, modified, and/or amended in the following manner:

---


**General:**

1. A walkthrough of the project will be conducted on Thursday, May 14<sup>th</sup> at 10:00 a.m. for all prospective bidders. Walkthrough to begin at the Town Park located at the southwest corner of Highway 25/County Road 61.
2. The agenda from the Pre-Bid meeting on May 5, 2020 @ 1:00 P.M. is attached.

3. As a clarification to the lane closure procedures, Contractor to notify Engineer a minimum of 72 hours prior to a requested lane closure. Engineer to notify ALDOT and run a press release to notify the public of the lane closure.
4. As a clarification to lane closure time restrictions, see Note 752 on Page 2G of the plans. Lane closures are not allowed for Christmas, New Years Day, Memorial Day, Labor Day, Independence Day, and Thanksgiving.
5. As a clarification to the aluminum sidewalk handrail, an alternate item for a Galvanized Steel Sidewalk Handrail (Item No. 517D-002) has been incorporated into the project.
6. All bidders are to use the attached revised Contract Schedule (3 pages) with revised the revised alternate galvanized handrail item.
7. As a clarification to the dimensions shown on the sidewalk handrail detail, the detail shown is a concept detail. Contractor may utilize a local fab shop or purchase handrail from a vendor. Exact dimensions of the cap rail and pickets may vary from different vendors. Contractor to submit shop drawings to Engineer for approval prior to fabrication or assembly.
8. As a clarification to the conduit for the Type 2 luminaires on the plans, Contractor may utilize the conduit for the Type 1 luminaires or install a dedicated conduit for the Type 2 luminaires. All conduits and wire feeds shall meet the National Electric Code.
9. The foundation for the Type 1 luminaires shall have a depth of 7'.
10. As a clarification to the electrical power supply from the Utility to the lighting control center, Utility to provide 240-volt feed to the service pole. ALDOT standard lighting control center details shows a 480-volt feed. Contractor to make necessary adjustments in lighting control center for 240-volt feed instead of 480 volt.
11. As a clarification to the Type 2 luminaires and the required transformer, transformer to be installed at the lighting control center. A 600-watt transformer shall be used. Contractor may utilize multiple smaller transformers in lieu of the 600-watt transformer. Transformer shall be sized and installed per manufacturer recommendations.
12. A panelboard schedule has not been completed for this project. Contractor to submit shop drawings to Engineer prior to construction detailing the panel schedule and lighting control center single line diagram with the 240-volt feed.
13. As a clarification to the pole for the Type 1 luminaires, the pole shall be a breakaway pole. Contractor shall supply breakaway couplings with the pole to mount onto the pole foundation.

This Addendum No. 2 shall be attached to the front of your set of Specifications and made a part of the Specifications and Contract Documents. Acknowledgment of receipt of Addendum No. 2 shall be noted on the Proposal Form

THE KELLEY GROUP, LLC.

By:  \_\_\_\_\_  
Will Glenn, P.E.

Addendum #2 is 9 total pages.  
This concludes Addendum #2.

# PRE-BID CONFERENCE AGENDA

TOWN OF WILSONVILLE  
 HIGHWAY 25 STREETSCAPE IMPROVEMENTS  
 ALDOT PROJECT NO. TAPNU-TA17(907)

TUESDAY, MAY 5, 2020 @ 1:00 P.M.

Note: This agenda is complimentary, for the purpose of review during this meeting only; It does not attempt to nor does it represent a total recapitulation of Project requirements, and does not change or alter same in any respect; Changes, *if any, will only be made by written Addendum.*

**General Review Items**

1	Welcoming remarks. Reminder to sign the attendance list.
2	Introduction of Owner: Town of Wilsonville Mayor Lee McCarty, (205) 669-6180
3	Introduction of Engineer: Project Engineer – Will Glenn, P.E., The Kelley Group, (256) 248-7030
4	<p><b><u>Scope of Work:</u></b></p> <ol style="list-style-type: none"> <li>1. Install approximately 2,650 LF of 5’ wide concrete sidewalk, concrete curb and gutter, lighting, handrail, &amp; various site furnishings</li> </ol> <p><b><u>General</u></b></p> <ol style="list-style-type: none"> <li>2. Construction shall conform to ALDOT Standard Specifications, 2018 Edition.</li> <li>3. CONTRACTORS shall review all FHWA &amp; ALDOT Requirements in the contract manual.</li> <li>4. All work to meet or exceed current ADA standards.</li> <li>5. Prime CONTRACTORS must be on ALDOT’s list of pre-qualified prime Contractors. Any CONTRACTOR who wishes to bid on the project and is not on ALDOT’s pre-qualified list shall notify the ENGINEER immediately.</li> <li>6. CONTRACTOR shall adhere to the Davis Bacon Wage rates.</li> <li>7. All concrete testing will be completed per ALDOT Standard Specifications. ENGINEER will schedule all material testing, CONTRACTOR to notify ENGINEER 48 hours prior to concrete/asphalt work.</li> <li>8. CONTRACTOR to review all Project Notes on Sheet 2C prior to submitting the bid.</li> <li>9. Concrete curb and gutter (Type C) (approximately 500 LF) to be installed along sidewalk alignment. See project plans.</li> <li>10. All sidewalk on the backside of the curb &amp; gutter shall have a black painted guardrail installed at the face of the curb and a pedestrian aluminum handrail installed on the backside of the sidewalk.</li> </ol>

	<p>11. Decorative post lighting to be installed along project alignment. Post lighting to be installed on handrail posts when sidewalk is adjacent to roadway.</p> <p>12. Stamped concrete sidewalk (approximately 330 CF) to be installed at beginning of project. Color &amp; texture to match existing stamped concrete at Wilsonville Park at Highway 25/CR 61. Contractor to submit color &amp; pattern samples to engineer for approval prior to construction.</p> <p>13. Two (2) wayfinding signs shall be installed at the Hwy 25/CR 61 intersection. See project plans for details &amp; location.</p> <p>14. A walk through of the alignment may be scheduled prior to the bid opening by emailing <a href="mailto:jessica@kelleynetwork.com">jessica@kelleynetwork.com</a> and requesting an appointment. <b>All requests must be received by Wednesday, May 13, 2020 at 3:00 P.M. CST.</b></p>
5	Construction plans available at Alabama Graphics for reproduction cost, non-refundable.
6	Every General Contractor <u>and every Subcontractor</u> should read and be familiar with all of the bid documents for this project.
7	Bid time, date, place - as indicated in Advertisement. Tuesday, May 19, 2020 @ 1:00 PM. at Wilsonville Town Hall located at 9905 North Main Street, Wilsonville, Alabama 35186.
8	<b>ALL</b> addendums shall be included in bid documents. At time of Pre-Bid, ONE addendum has been issued.
9	<b>ALL</b> questions shall be submitted in writing to Will Glenn, P.E. and emailed to <a href="mailto:will@kelleynetwork.com">will@kelleynetwork.com</a>

**Design / Construction Items**

1	Bid Bond NTE 5% or \$10,000 is required to be submitted with your bid.									
2	<p>Time for Completion: Ninety (90) working days for Final Payment</p> <p>Schedule of Liquidated Damages:</p> <table border="0"> <thead> <tr> <th><i>More than:</i></th> <th><i>To and including:</i></th> <th><i>Work Day:</i></th> </tr> </thead> <tbody> <tr> <td>\$1,000,000</td> <td>\$2,000,000</td> <td>\$2,500</td> </tr> <tr> <td>\$2,000,000</td> <td>\$5,000,000</td> <td>\$3,300</td> </tr> </tbody> </table>	<i>More than:</i>	<i>To and including:</i>	<i>Work Day:</i>	\$1,000,000	\$2,000,000	\$2,500	\$2,000,000	\$5,000,000	\$3,300
<i>More than:</i>	<i>To and including:</i>	<i>Work Day:</i>								
\$1,000,000	\$2,000,000	\$2,500								
\$2,000,000	\$5,000,000	\$3,300								

**END OF PRE-BID CONFERENCE AGENDA**

QUESTIONS/COMMENTS

All questions will be addressed in Addendum Format.

- 
- 
- 
- 
-

**PROJECT No. TAPNU-TA17(907)**

**CONTRACT SCHEDULE (ADDENDUM #2)**

WITH SPECIAL REGARD TO SPECIFICATION SECTION 102.06, "PREPARATION OF PROPOSAL", **AS REVISED BY THE SPECIAL PROVISIONS**, THE FOLLOWING REPRESENTS THE BIDDER'S SCHEDULE OF CONTRACT UNIT PRICES FOR THIS PROPOSAL (bidder to complete below):

**Base Bid**

LINE NO.	ITEM NO.	DESCRIPTION	QUANTITY & UNIT		UNIT PRICE		AMOUNT BID	
1	201A-002	Clearing and Grubbing (Maximum Allowable Bid \$4,000) (Approx. 1 Acre)	1	Lump Sum	\$		\$	
2	206C-001	Removing Concrete Pavement	90	Sq. Yd.	\$		\$	
3	206C-002	Removing Concrete Slope Paving	16	Sq. Yd.	\$		\$	
4	206C-008	Removing Concrete Median	11	Sq. Yd.	\$		\$	
5	206D-000	Removing Pipe	5	Lin. Ft.	\$		\$	
6	206D-002	Removing Curb	28	Lin. Ft.	\$		\$	
7	206D-011	Removing Fence	11	Lin. Ft.	\$		\$	
8	206E-050	Removing Sloped Paved Headwall	1	Each	\$		\$	
9	210A-000	Unclassified Excavation	30	Cu. Yd.	\$		\$	
10	210D-001	Borrow Excavation (loose truckbed measurement)	390	Cu. Yd.	\$		\$	
11	301A-012	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness	178	Sq. Yd.	\$		\$	
12	517D-001	Aluminum Sidewalk Handrail	857	Lin. Ft.	\$		\$	
13	517H-000	Ornamental Metal Bench	2	Each	\$		\$	
14	530A-101	18" Roadway Pipe (Class 3 R.C.) (Extension)	11	Lin. Ft.	\$		\$	
15	600A-000	Mobilization	1	Lump Sum	\$		\$	
16	610A-000	Loose RipRap, Class 1, 6" Thick	98	Sq. Yd.	\$		\$	
17	610D-000	Filter Blanket, Geotextile	98	Sq. Yd.	\$		\$	
18	614A-000	Slope Paving	5	Cu. Yd.	\$		\$	
19	618A-000	Concrete Sidewalk, 4" Thick	1,150	Sq. Yd.	\$		\$	
20	618B-003	Concrete Driveway, 6" Thick (Includes Wire Mesh)	445	Sq. Yd.	\$		\$	
21	619A-002	18" Roadway Pipe End Treatment, Class 1	1	Each	\$		\$	
22	620A-000	Minor Structure Concrete	1	Cu. Yd.	\$		\$	

23	623A-000	Concrete Gutter	56	Lin. Ft.	\$		\$	
24	623B-002	Concrete Curb, Type A	33	Lin. Ft.	\$		\$	
25	623C-000	Combination Curb & Gutter, Type C	493	Lin. Ft.	\$		\$	
26	630A-021	Steel Beam Guardrail, Class A, Type 2 (Steel Posts)	791	Lin. Ft.	\$		\$	
27	630C-001	Guardrail End Anchor, Type 8	3	Each	\$		\$	
28	630C-080	Guardrail End Anchor, Type 20 Series (MASH)	3	Each	\$		\$	
29	650A-000	Topsoil	100	Cu. Yd.	\$		\$	
30	652A-100	Seeding	1	Acre	\$		\$	
31	654A-001	Solid Sodding (Bermuda)	825	Sq. Yd.	\$		\$	
32	656A-010	Mulching	1	Acre	\$		\$	
33	659C-002	Erosion Control Product, Type S2	395	Sq. Yd.	\$		\$	
34	665A-000	Temporary Seeding	1	Acre	\$		\$	
35	665B-001	Temporary Mulching	1	Ton	\$		\$	
36	665J-002	Silt Fence	2,300	Lin. Ft.	\$		\$	
37	665O-001	Silt Fence Removal	2,300	Lin. Ft.	\$		\$	
38	665P-005	Inlet Protection, Stage 3 or 4	3	Each	\$		\$	
39	665Q-002	Wattle	490	Lin. Ft.	\$		\$	
40	703A-002	Traffic Control Markings, Class 2, Type A	400	Sq. Ft.	\$		\$	
41	740B-000	Construction Signs	176	Sq. Ft.	\$		\$	
42	740D-000	Channelizing Drums	50	Each	\$		\$	
43	740E-000	Cones (36 Inches High)	50	Each	\$		\$	
44	740M-001	Ballast for Cone	50	Each	\$		\$	
45	750C-010	Pole Foundation, Roadway	21	Each	\$		\$	
46	750D-200	Electrical Junction Box, Type 1	3	Each	\$		\$	
47	750E-112	Conduit, 1 Inch, Rigid NonMetallic	2,590	Lin. Ft.	\$		\$	
48	750F-023	Conductor, #8 AWG	7,770	Lin. Ft.	\$		\$	
49	750H-005	Service Pole	1	Each	\$		\$	
50	750I-015	Lighting Control Center	1	Each	\$		\$	
51	750T-010	Decorative LED Linear Luminaire	21	Each	\$		\$	



52	750Z-220	Roadway Lighting	1	Lump Sum	\$		\$		
53	770N-000	Garbage Deposities	2	Each	\$		\$		
54	771F-000	Under Sidewalk Cross Drain	10	Each	\$		\$		
55	792A-001	Site Furnishings (Wayfinding Sign)	2	Each	\$		\$		
56	792A-002	Site Furnishings (Stamped Concrete Sidewalk)	188	Sq. Yd.	\$		\$		
<b>TOTAL BASE BID AMOUNT:</b>							\$		

**Alternate Bid**

LINE NO.	ITEM NO.	DESCRIPTION	QUANTITY & UNIT		UNIT PRICE	AMOUNT BID		
57	517D-002	Galvanized Steel Sidewalk Handrail	857	Lin. Ft.	\$		\$	
<b>TOTAL ALTERNATE BID:</b>							\$	